

SECTION 092116**GYPSUM BOARD ASSEMBLIES****PART 1 GENERAL****1.1 GENERAL REQUIREMENTS**

- A. Work of this Section, as shown or specified, shall be in accordance with the Contract Documents.

1.2 SECTION INCLUDES

- A. Work of this Section includes all labor, materials, equipment, and services necessary to complete the gypsum board assemblies as shown on the drawings and/or specified herein, including, but not limited to, the following:
 - 1. Gypsum board work for partitions, ceilings, column enclosures, furring, and elsewhere where gypsum drywall work is shown on drawings.
 - 2. Metal supports for gypsum drywall construction.
 - 3. Acoustical insulation for gypsum drywall work.
 - 4. Sealant for gypsum drywall work.
 - 5. Concealed metal reinforcing for attachment of railings, toilet partitions, and other items supported on drywall partitions and walls.
 - 6. Taping and finishing of drywall joints.
 - 7. Installing rings and frames in drywall surfaces for grilles, registers and lighting fixtures.
 - 8. Gypsum shaftwall construction.
 - 9. Bracing and connections.

1.3 RELATED SECTIONS

- A. Thermal Insulation - Section 072100.
- B. Steel Doors and Frames - Section 081113.
- C. Painting and Finishing - Section 099100.
- D. Rings for grilles, registers and light fixtures - Division 23 and 26.

1.4 QUALITY ASSURANCE

- A. The following standards, as well as other standards which may be referred to in this Section, shall apply to the work of this Section:
 - 1. The Gypsum Construction Handbook, latest edition, USG.

2. ASTM A 568 "Standard Specification for Steel, Sheet, Carbon, and High-Strength, Low-Alloy, Hot-Rolled and Cold-Rolled, General Requirements For"
 3. ASTM C 475 "Standard Specification for Joint Treatment Materials For Gypsum Wallboard Construction"
 4. ASTM C 645 "Standard Specification for Non-Structural Steel Framing Members"
 5. ASTM C 754 "Standard Specification for Installation of Steel Framing Members to Receive Screw Attached Gypsum Panel Products"
 6. ASTM C 840 "Standard Specification for Application and Finishing of Gypsum Board"
 7. ASTM C 919 "Standard Specification for Use of Sealants in Acoustical Applications"
 8. ASTM C 954 "Standard Specification for Steel Drill Screws For the Application of Gypsum Board or Metal Plaster Bases to Steel Studs From 0.033 in. to 0.112 in. in Thickness"
 9. ASTM C 1002 "Standard Specification for Steel Self-Piercing Tapping Screws For the Application of Gypsum Board"
 10. ASTM C 1177 "Standard Specification for Glass Mat Gypsum Substrate for Use at Sheathing"
 11. ASTM C 1178 "Standard Specification for Glass Mat Water Resistant Gypsum Backing Board"
 12. ASTM C 1278 "Standard Specification for Fiber-Reinforced Gypsum Panel"
 13. ASTM C 1396 "Standard Specification for Gypsum Board"
 14. ASTM D 3273 "Standard Test Method for Resistance to Growth of Mold on the Surface of Interior Coatings in an Environmental Chamber"
- B. Allowable Tolerances: 1/32" offsets between planes of board faces, and 1/16" in 8'-0" for plumb, level, warp and bow.
- C. System Design Load
1. Provide standard drywall wall assemblies designed and tested by manufacturer to withstand a lateral load of 5 lbs. per sq. ft. for the maximum wall height required, and with deflection limited to L/240 of partition height.
 - a. Drywall assemblies with tile finish shall have a deflection limit of L/360.
 2. Provide drywall ceiling assemblies designed, fabricated and installed to have a deflection not to exceed L/360.
- D. Fire-Resistance Rating: Where gypsum drywall with fire resistance ratings are indicated, provide materials and installations which are identical with those of applicable assemblies tested per ASTM E 119 by fire testing laboratories, or to design designations in UL "Fire Resistance Directory" or in listing of other testing agencies acceptable to authorities having jurisdiction, and compliant with UL Test #2079; criteria for cycle movement for all field height wall sections requiring allowance for vertical deflection within framing details.

- E. Installer: Firm with not less than three (3) years of successful experience in the installation of specified materials.
- F. Comply with New York City Section 32-05 of Chapter 32 of Title 1 of the Official Compilation of the Rules of the City of New York regarding "Impact Resistant Stair and Elevator Enclosures" when such enclosures are of gypsum drywall construction.

1.5 SUBMITTALS

- A. Submit shop drawing for each drywall partition, furring and ceiling system showing size and gauges of framing members, hanger and anchorage devices, wallboard types, insulation, sealant, methods of assembly and fastening, control joints indicating column lines, corner details, joint finishing and relationship of drywall work to adjacent work.
- B. Samples: Each material specified herein, 12" x 12", or 12" long, or in manufacturer's container, as applicable for type of material submitted.
- C. Manufacturer's Literature: Submit technical and installation instructions for each drywall partition, furring and ceiling system specified herein, and for each fire-rated and sound-rated gypsum board assembly. Submit other data as required to show compliance with these specifications, including data for mold resistant joint compound.
- D. Test Reports: This Contractor shall submit test report, obtained by drywall manufacturer, indicating conformance of drywall assemblies to required fire ratings and sound ratings.

1.6 PRODUCT HANDLING AND PROTECTION

- A. Deliver, store and handle drywall work materials to prevent damage. Deliver materials in their original, unopened containers or bundles, and store where protected from moisture, damage and from exposure to the elements. Store wallboard in flat stacks.
- B. Protect wallboard from becoming wet.

1.7 ENVIRONMENTAL CONDITIONS

- A. Provide and maintain minimum temperature of fifty-five (55) degrees F. and adequate ventilation to eliminate excessive moisture within the building in the area of the drywall work for at least twenty-four (24) hours, prior to, during and after installation of drywall work. Installation shall not start until windows are glazed and doors are installed, unless openings are temporarily closed. Space above suspended ceilings shall be vented sufficiently to prevent temperature and pressure build up.

1.8 JOB MOCK-UP

- A. At a suitable location, where directed by the Commissioner, lay up a portion of a finished wall and ceiling demonstrating the quality of work, including finishing, to be obtained under this Section. Omit drywall boards in locations as directed by the Commissioner to show stud spacing and attachments; after acceptance, complete assembly.
- B. Adjust the finishing techniques as required to achieve the finish required by the Commissioner as described in this Section of these specifications.
- C. Upon approval of the mock-up, the mock-up may be left in place as a portion of the finished work of this Section.
- D. All drywall work shall be equal in quality to approved mock-up.

PART 2 PRODUCTS**2.1 MANUFACTURERS**

- A. Acceptable Manufacturers for Gypsum Drywall Panels and Accessories: Materials specified below, unless noted otherwise or specified herein, are those of U.S. Gypsum Co. Equivalent materials of Georgia Pacific, Lafarge North America, or National Gypsum Co. meeting specification requirements are acceptable.
 - 1. All drywall products must be manufactured in North America.
- B. Acceptable Manufacturers for Metal Supports of Drywall Assemblies: Unless otherwise noted, provide products manufactured by Dietrich Metal Framing, Super Stud Building Products, Marino/Ware, Clark Western or approved equal.

2.2 METAL SUPPORTS

- A. Metal Floor and Ceiling Runners
 - 1. Channel Type: Formed from 20 U.S. Std. gauge (unless otherwise noted) galvanized steel, width to suit channel type metal studs. Use 20 ga. top runners with 1-1/4" minimum flanges.
 - 2. Ceiling runners and head of wall connections at rated partitions shall conform to UL #2079 for cycle movement. Provide positive mechanical connection of framing to structure, allowing for vertical movement within connections. Minimum of 20 ga. galvanized steel for clips, 25 ga. galvanized steel for ceiling runners. Providing a friction free – anti-seizure movement capacity.
 - a. As manufactured by the Steel Network, VertiClip or VertiTrack or equal made by Metal-Lite Inc.
 - b. FireTrak (including stud clips) by FireTrak Corp. or equal made by Metal-Lite Inc.
 - 3. "J" Type: Formed from 20 U.S. Std. gauge galvanized steel, 1" x 2-1/2" or 4" wide (to suit detail) x 2-1/4" (for shaft wall).
- B. Metal Studs, Framing and Furring
 - 1. Channel Type Studs: Channel type with holes for passage of conduit formed from minimum 20 U.S. Std. gauge (unless heavier gauge is required to meet deflection limits) galvanized steel, width as shown on drawings.
 - 2. Furring Channels: Hat shaped, formed from galvanized steel, 25 U.S. Std. gauge.
 - 3. "C-H," "CT," or "I" Type Stud: 1-1/2" x 2-1/2", 4" or 6" wide (to suit detail) galvanized steel. Use for shaft wall construction; gauge and size as required to meet deflection limits given herein.
 - 4. Double "E" Type Stud or "J" Track with Holding Tabs: 2" x 2-1/2", 4" or 6" wide (to suit detail) galvanized steel. Use for shaft wall construction; gauge and size as required to meet deflection limits given herein.
 - 5. Continuous 16 gauge x 8" wide steel wall plate screwed to studs as required for support of railings, toilet partitions and other items supported on drywall partitions and walls.

C. Suspended Ceiling and Fascia Supports

1. Main Runners: 1-1/2" steel channels, cold rolled at 0.475 lbs. per ft., rust-inhibitive paint finish.
2. Furring Members: Screw-type hat-shaped furring channels of 25 ga. zinc-coated steel; comply with ASTM C 645.
3. Hangers: Galvanized, 1" x 3/16" flat steel slats capable of supporting 5x calculated load supported.
4. Hanger Anchorages: Provide inserts, clips, bolts, screws and other devices applicable to the required method of structural anchorage for ceiling hangers. Size devices for 5x calculated load supported.
5. Furring Anchorages: 16 ga. galvanized wire ties, manufacturer's standard clips, bolts or screws as recommended by furring manufacturer.

D. All galvanized steel members shall have coating conforming to ASTM A 653, G60.

2.3 GYPSUM WALLBOARD TYPES

- A. Gypsum Wall Board: 5/8" thick "Sheetrock," 48" wide, in maximum lengths available to minimize end-to-end butt joints.
- B. Fire Rated Gypsum Wall Board: 5/8" thick "Sheetrock Firecode C," or "Firecheck Type C" by Lafarge, 48" wide, in maximum lengths available to minimize end-to-end butt joints.
- C. Water Resistant Backing Board for Tile Finish: 5/8" thick, 3' x 6', "Durock Tile Backer Board" or "Dens-Shield Tile Backer Board" by Georgia Pacific. Cover joints with a pressure sensitive woven glass fiber tape equal to Imperial Type P Tape.
- D. Moisture/Mold Resistant Gypsum Wall Board (for wet areas not scheduled to receive ceramic tile, or where fire rating is required): 5/8" thick "Mold Tough," "Mold Tough FR," by U.S. Gypsum, "DensArmor Plus" by Georgia Pacific or Lafarge "Mold Defense" and/or Lafarge "Mold Defense Type X," 48" wide, in maximum lengths available to minimize end-to-end butt joints.
 1. Board must have a rating of 10 per ASTM D 3273 with a core that meets ASTM C 1396, Section 6 or ASTM C 1658.
- E. Mold Resistant Shaft Wall Liner: Solid gypsum board liner for shaft wall construction, 1" thick, 24" wide, as required to suit condition, by standard lengths as required, beveled edges. Provide "Mold Tough Liner Panel," "DensGlass Ultra Shaft Guard" by Georgia Pacific, or Lafarge "Mold Defense Shaftliner Type X" and/or Lafarge "Weather Defense Shaftliner Type X."
 1. Liner board must have a rating 10 per ASTM D 3273 with a core that meet ASTM C 1396 Section 6 and ASTM C 442.
- F. Mold Resistant Paperless Wall Board (at all perimeter walls and wet shafts): 1/2" and 5/8" thick as indicated on drawings, 48" wide "DensArmor Plus" by Georgia Pacific, "Mold Tough" by USG, Lafarge "Mold Defense" and/or Lafarge "Mold Defense Type X," or approved equal that has a rating of 10 per ASTM D 3273 with core that meets ASTM C 1396, Section 6 or ASTM C1658.

2.4 ACCESSORIES

- A. Acoustical Insulation: Paper-less, non-combustible, semi-rigid mineral fiber mat, 2" thick, in walls (unless otherwise indicated), 3 lb./cu. ft. maximum density; Thermafiber LLC "Thermafiber," or approved equal.
- B. Fasteners for Wall Board: USG Brand Screws; Type S Bugle Head for fastening wallboard to lighter gauge interior metal framing (up to 20 ga.). Type S-12 Bugle Head for fastening wallboard to heavier gauge interior metal framing (20 ga. to 12 ga.); Type S and Type S-12 Pan Head for attaching metal studs to door frames and runners; and Type G Bugle Head for fastening wallboard to wall board. Lengths specified below under "Part 3 - Execution" Articles and as recommended by drywall manufacturer.
- C. Laminating Adhesive: "Sheetrock Brand Joint Compound."
- D. Metal Trim - Corner Beads: For 90 degree External Corners - "Dur-A-Bead" No. 103, 27 U.S. Std. ga. galvanized steel, 1-1/4" x 1-1/4", for 90 degree external corners.
- E. Metal Trim - Edge Beads: "Sheetrock Brand Paper Faced Metal Bead and Trim."
- F. Metal Trim Treatment Materials and Joint Treatment Materials for Gypsum Drywall Boards: Paper tape for joint reinforcing; Setting Type (Durabond 90) or Lightweight Setting Type Joint Compound for taping and topping; and Ready Mix Compound for finishing.
 - 1. For mold-resistant drywall, water resistant drywall, and tile backer board, use glass mesh tape with setting joint compound that is rated 10 when tested in accordance with ASTM D 3273 and evaluated in accordance with ASTM D 3274. Acceptable joint compound is "Rapid Set One Pass" made by CTS Cement Manufacturing Corp. or "Rapid Joint" manufactured by Lafarge North America or approved equal meeting standards noted herein.
- G. Control Joints: No. 0.093, USG.
- H. Acoustical Sealant: USG "Acoustical Sealant" or "Tremco Acoustical Caulking" of Tremco Mfg. Co., or approved equal.
- I. Neoprene Gaskets: Conform to ASTM D 1056.

PART 3 EXECUTION

3.1 INSPECTION

- A. Examine the areas and conditions where gypsum board assemblies are to be installed and correct any conditions detrimental to the proper and timely completion of the work. Do not proceed with the work until unsatisfactory conditions are corrected to permit proper installation of the work.

3.2 GENERAL INSTALLATION REQUIREMENTS

- A. General
 - 1. Install drywall work in accordance with drywall manufacturer's printed instructions and as indicated on drawings and specified herein.

2. All metal framing for drywall partitions shall extend from floor to underside of structural deck above. Provide for vertical deflection with positive mechanical connections of framing members to structure.
3. Provide concealed reinforcement, 16 ga. thick by eight (8) inches wide or as detailed or as recommended by manufacturer, for attachment of railings, toilet partitions, and other items to be supported on the partitions which cannot be attached to the metal framing members. Concealed reinforcement shall span between metal studs and be attached thereto using two (2) self-tapping pan head screws at each stud.
 - a. Back of drywall shall be scored or notched to prevent bulging out where reinforcement plate occurs.
- B. Fire-Rated Assemblies: Install fire-rated assemblies in accordance with requirements of authorities having jurisdiction, Underwriters' Laboratories and test results obtained and published by the drywall manufacturer, for the fire-rated drywall assembly types indicated on the drawings.
- C. Acoustical Assemblies: Install acoustically-rated assemblies to achieve a minimum STC as noted on drawings, in accordance with test results obtained and published by the drywall manufacturer, for the drywall assembly type indicated on the drawings.
- D. Sealant
 1. Install continuous acoustical sealant bead at top and bottom edges of wallboard where indicated or required for sound rating as wallboard is installed, and between metal trim edge beads and abutting construction.
 2. Install acoustical sealant in 1/8" wide vertical control joints within the length of the wall or partitions, and in all other joints, specified below under "Control Joints." Install bead of acoustical sealant around electric switch and outlet boxes, piping, ducts, and around any other penetration in the wallboard; place sealant bead between penetrations and edge of wallboard.
 3. Where sealant is exposed to view, protect adjacent surfaces from damage and from sealant material, and tool sealant flush with and in same plane as wallboard surface. Sealant beads shall be 1/4" to 3/8" diameter.
- E. Wall Board Application
 1. Do not install wallboard panels until steel door frames are in place; coordinate work with Section 081113, "Steel Doors and Frames."
 2. See drawings for all board types. Use fire-rated wallboard for fire-rated assemblies. Use sag-resistant wallboard for ceilings. Use water-resistant wallboard where indicated on drawings and where wallboard would be subject to moisture. Install water-resistant wallboard in full, large sheets (no scraps) to limit number of butt joints.
 3. Apply wallboard with long dimension parallel to stud framing members, and with abutting edges occurring over stud flanges.
 4. Install wallboard for partitions from floor to underside of structure above and secure rigidly in place by screw attachment, unless otherwise indicated.

5. Provide "Thermafiber" safing insulation meeting standards of Section 078413 at flutes of metal deck where partitions carry up to bottom of metal deck.
 6. Neatly cut wallboard to fit around outlets, switch boxes, framed openings, piping, ducts, and other items which penetrate wallboard; fill gaps with acoustic sealant.
 7. Where wallboard is to be applied to curved surfaces, dampen wallboard on back side as required to obtain required curve. Finish surface shall present smooth, even curve without fluting or other imperfections.
 8. Screw fasten wallboard with power-driven electric screw driver, screw heads to slightly depress surface of wallboard without cutting paper, screws not closer than 3/8" from ends and edges of wallboard.
 9. Where studs are doubled-up, screw fasten wallboard to both studs in a staggered pattern.
- F. Metal Trim: Install and mechanically secure in accordance with manufacturer's instructions; and finish with three (3) coats of joint compound, feathered and finish sanded smooth with adjacent wallboard surface, in accordance with manufacturer's instructions.
1. Corner Beads: Install specified corner beads in single lengths at all external corners, unless corner lengths exceed standard stock lengths.
 2. Edge Beads: Install specified edge beads in single lengths at all terminating edges of wallboard exposed to view, where edges abut dissimilar materials, where edges would be exposed to view, and elsewhere where shown on drawings. Where indicated on drawings, seal joint between metal edge bead and adjoining surface with specified gasket, 1/8" wide minimum and set back 1/8" from face of wallboard, unless other size and profile indicated on drawings.
 3. Casing beads shall be set in long lengths, neatly butted at joints. Provide casing beads at juncture of board and vertical surfaces and at exposed perimeters.
- G. Control Joint Locations: Gypsum board surfaces shall be isolated with control joints where:
1. Ceiling abuts a structural element, dissimilar wall or other vertical penetration.
 2. Construction changes within the plane of the partition or ceiling.
 3. Shown on approved shop drawings.
 4. Ceiling dimensions exceed thirty (30) feet in either direction.
 5. Wings of "L," "U," and "T" shaped ceiling areas are joined.
 6. Expansion or control joints occur in the structural elements of the building.
 7. Shaftwall runs exceed 30' without interruption.
 8. Partition or furring abuts a structural element or dissimilar wall or ceiling.
 9. Partition or furring runs exceed 30' without interruption.

10. Where control joints are required, ceiling height door frames may be used as control joints. Less than ceiling height frames shall have control joints extending to the ceiling from both corners.

H. Joint Treatment and Spackling

1. Joints between face wallboards in the same plane, joints at internal corners of intersecting partitions and joints at internal corners of intersections between ceilings and walls or partitions shall be filled with joint compound.
2. Screw heads and other depressions shall be filled with joint compound. Joint compound shall be applied in three (3) coats, feathered and finish surface sanded smooth with adjacent wallboard surface, in accordance with manufacturer's instructions. Treatment of joints and screw heads with joint compound is also required where wallboard will be covered by finish materials which require a smooth surface, such as vinyl wall coverings.

3.3 FURRED WALLS AND PARTITIONS

- A. Use specified metal furring channels. Run metal furring channel framing members vertically, space sixteen (16) inches o.c. maximum. Fasten furring channels to concrete or masonry surfaces with power-driven fasteners or concrete stub nails spaced sixteen (16) inches o.c. maximum through alternate wing flanges (staggered) of furring channel. Furring channels shall be shimmed as necessary to provide a plumb and level backing for wallboard. At inside of exterior walls, an asphalt felt protection strip shall be installed between each furring channel and the wall. Furring channel and splices shall be provided by nesting channels at least eight (8) inches and securely anchoring to concrete or masonry with two (2) fasteners in each wing.
- B. Wallboard Installation: Same as specified under Article 3.4 - "Metal Stud Partitions."

3.4 METAL STUD PARTITIONS

- A. Runner Installation: Use channel type. Align accurately at floor according to partition layout. Anchor runners securely sixteen (16) inches o.c. maximum with power-driven anchors to floor slab, with power-driven anchors to structural slab above. See "Stud Installation" below for runners over heads of metal door frames. Where required, carefully remove sprayed-on fireproofing to allow partition to be properly installed. Re-apply sprayed-on fireproofing; using original sprayed-on fireproofing system, to surfaces damaged and in thicknesses required to maintain fire rating of steel members.
- B. Stud Installation
 1. Use channel type, positioned vertically in runners, spaced as noted on drawings, but not more than sixteen (16) inches o.c.
 2. Anchor studs to floor runners with screw fasteners. Provide snap-in or slotted hole slip joint bolt connections of studs to ceiling runners leaving space for movement. Anchor studs at partition intersections, partition corners and where partition abuts other construction to floor and ceiling runners with sheet metal screws through each stud flange and runner flange.
 3. Connection at ceiling runner for non-rated partitions shall be snap-in or slotted hole slip joint bolt connection that shall allow for movement. Seal studs abutting other construction with 1/8" thick neoprene gasket continuously between stud and abutting construction.

4. Connections for fire rated partitions at ceiling runners shall conform to UL Design #2079.
 5. Install metal stud horizontal bracing wherever vertical studs are cut or wallboard is cut for passage of pipes, ducts or other penetrations, and anchor horizontal bracing to vertical studs with sheet metal screws.
 6. At jambs of door frames and borrowed light frames, install doubled-up studs (not back to back) from floor to underside of structural deck, and securely anchor studs to jamb anchors of frames and to runners with screws. Provide cross braces from hollow metal frames to underside of slab.
 7. Over heads of door frames, install cut-to-length section of runner with flanges slit and web bent to allow flanges to overlap adjacent vertical studs, and securely anchor runner to adjacent vertical studs with sheet metal screws. Install cut-to-length vertical studs from runner (over heads of door frame) to ceiling runner sixteen (16) inches maximum o.c. and at vertical joints of wallboard, and securely anchor studs to runners with sheet metal screws.
 8. At control joints, in field of partition, install double-up studs (back to back) from floor to ceiling runner, with 1/4" thick continuous compressible gasket between studs. When necessary, splice studs with eight (8) inches minimum nested laps and attach flanges together with two (2) sheet metal screws in each flange. All screws shall be self-tapping sheet metal screws.
- C. Runners and Studs at Chase Wall: As specified above for "Runners" and "Studs" and as specified herein. Chase walls shall have either a single or double row of floor and ceiling runners with metal studs sixteen (16) inches o.c. maximum and positioned vertically in the runners so that the studs are opposite each other in pairs with the flanges pointing in the same direction. Anchor all studs to runner flanges with sheet metal screws through each stud flange and runner flange following requirements of paragraph 3.4, B. Provide cross bracing between the rows of studs by attaching runner channels or studs set full width of chase attached to vertical studs with one self-tapping screw at each end. Space cross bracing not over thirty-six (36) inches o.c. vertically.
- D. Wallboard Installation - Single Layer Application (Screw Attached)
1. Install wallboard with long dimension parallel to framing member and with abutting edge joints over web of framing member. Install wallboard with long dimension perpendicular to framing members above and below openings in drywall extending to second stud at each side of opening. Joints on opposite sides of wall shall be arranged so as to occur on different studs.
 2. Boards shall be fastened securely to metal studs with screws as specified. Where a free end occurs between studs, back blocking shall be required. Center abutting ends over studs. Correct work as necessary so that faces of boards are flush, smooth, true.
 3. Wallboard screws shall be applied with an electric screw gun. Screws shall be driven not less than 3/8" from ends or edges of board to provide uniform dimple not over 1/32" deep. Screws shall be spaced twelve (12) inches o.c. in the field of the board and 8" o.c. staggered along the abutting edges.
 4. All ends and edges of wallboard shall occur over screwing members (studs or furring channels). Boards shall be brought into contact but shall not be forced into place. Where ends or edges abut, they shall be staggered. Joints on opposite sides of a partition shall be so arranged as to occur on different studs.

5. At locations where piping receptacles, conduit, switches, etc., penetrate drywall partitions, provide non-drying sealant and an approved sealant stop at cut board locations inside partition.
- E. Wallboard Installation - Double-Layer Application
1. General: See drawings for wallboard partition types required.
 2. First Layer (Screw Attached): Install as described above for single layer application.
 3. Second Layer (Screw Attached): Screw attach second layer, unless laminating method of attachment indicated on drawings or necessary to obtain required sound rating or fire rating. Install wallboard vertically with vertical joints offset thirty-four (34) inches from first layer joints and staggered on opposite sides of wall. Attach wallboard with 1-5/8" screws sixteen (16) inches o.c. along vertical joints and sixteen (16) inches o.c. in the field of the wallboard. Screw through first layer into metal framing members.
 4. Second Layer (Laminated): Install wallboard vertically. Stagger joints of second layer from first layer joints. Laminate second layer with specified laminating adhesive in beads or strips running continuously from floor to ceiling in accordance with manufacturer's instructions. After laminating, screw wallboard to framing members with 1-5/8" screws, spaced twelve (12) inches o.c. around perimeter of wallboard.
- F. Wallboard Installation - Laminated Application: Where laminated wallboard is indicated, use specified laminating adhesive, install wallboard vertically and maintain tolerances as specified for screw attached wallboard.
- G. Insulation Installation: Install where indicated on drawings. Place blanket tightly between studs.
- H. Deflection of Structure Above: To allow for possible deflection of structure above partitions, provide top runners for non-rated partitions with 1-1/4" minimum flanges and do not screw studs or drywall to top runner. Where positive anchorage of studs to top runner is required, anchorage device shall be by means of slotted hole (in clip connection with screw attachment to web of steel through bushings located in slots of clips), or other anchorage device approved by Commissioner.
- I. Control Joints
1. Leave a 1/2" continuous opening between gypsum boards for insertion of surface mounted joint.
 2. Back by double framing members.
 3. Attach control joint to face layer with 9/16" galvanized staples six (6) inches o.c. at both flanges along entire length of joint.
 4. Provide two (2) inch wide gypsum panel strip or other adequate seal behind control joint in fire rated partitions and partitions with safing insulation.

3.5 DRYWALL FASCIAS AND CEILINGS

- A. Furnish and install inserts, hanger clips and similar devices in coordination with other work.

- B. Secure hangers to inserts and clips. Clamp or bolt hangers to main runners.
- C. Space main runners 4'-0" o.c. and space hangers 4'-0" o.c. along runners, except as otherwise shown.
- D. Level main runners to a tolerance of 1/4" in 12'-0", measured both lengthwise on each runner and transversely between parallel runners.
- E. Metal Furring Channels: Space sixteen (16) inches o.c. maximum. Attach to 1-1/2" main runner channels with furring channel clips (on alternate sides of main runner channels). Furring channels shall not be let into or come in contact with abutting masonry walls. End splices shall be provided by nesting furring channels no less than eight (8) inches and securely wire tying. At any openings that interrupt the furring channels, install additional cross reinforcing to restore lateral stability.
- F. Mechanical accessories, hangers, splices, runner channels and other members used in suspension system shall be of metal, zinc coated, or coated with rust inhibitive paint, of suitable design and of adequate strength to support units securely without sagging, and such as to bring unit faces to finished indicated lines and levels.
 - 1. Provide special furring where ducts are over two (2) feet wide.
- G. Apply board with its long dimension at right angles to channels. Locate board butt joints over center of furring channels. Attach board with one (1) inch self-drilling drywall screws twelve (12) inches o.c. in field of board at each furring channel; eight (8) inches o.c. at butt joints located not less than 3/8" from edges.

3.6 SHAFT WALLS

- A. Runner Installation: Use "J" metal runners at floor and ceiling, with the short leg toward finish side of wall. Securely attach runners to structural supports with power-driven fasteners at both ends and twenty-four (24) inches o.c.
- B. Shaft Wall Liner: Cut shaft wall liner panels one (1) inch less from floor to ceiling height and erect vertically between J-runners.
- C. C-H Studs: Cut metal studs 3/8" to not more than 1/2" less than floor to ceiling height and install between shaft wall liner panels so that panels are fitted snugly into the one (1) inch wide "H", "T" or "I" portion of the stud. Space studs twenty-four (24) inches o.c., unless otherwise indicated on drawings. Install full-length steel E-Studs or J-runners vertically at T-intersections, corners, door jambs, and columns. Install full length E-Studs or J-runners over shaft wall liner both sides of closure panels. Frame openings cut within a liner panel with J-Runner around perimeter. For openings, frame with vertical E-Stud or J-runner at edges, horizontal runner at head and sill, and reinforcing as shown on the drawings. Suitably frame all openings to maintain structural support for wall. Over metal doors, install a cut to length section of runner and attach to strut-studs with clip angles and 3/8" Type S Screws space twelve (12) inches o.c.
- D. Wallboard Installation - Double Layer Installation: Erect gypsum wallboard base layer horizontally one side of studs with end joints staggered. Fasten base layer panels to studs with one (1) inch Type S screws twenty-four (24) inches o.c. Caulk perimeter of base layer panels. Apply gypsum wallboard face layer vertically over base layer with joints staggered and attached with 1-5/8" Type S screws staggered from those in base, spaced eight (8) inches o.c. and driven into studs.
- E. Wallboard Installation (Where Both Sides of Shaft Wall are Finished): Apply gypsum wallboard face layers vertically both sides of studs. Stagger joints on opposite partition

sides. Fasten panels with one (1) inch or two (2) inches Type S screws spaced eight (8) inches o.c. in field and along edges into studs.

- F. Where handrails are indicated for direct attachment to drywall shaft system, provide not less than a sixteen (16) ga. x eight (8) inches wide galvanized steel reinforcement strip, accurately positioned and secured to studs and concealed behind not less than one 1/2" thick course of gypsum board in the system.
- G. Integrate stair hanger rods with drywall shaft system by locating cavity of system as required to enclose rods.

3.7 ERECTION AT COLUMN ENCLOSURES

- A. Metal furring supports shall be provided under work of this Section, and shall be cut to lengths as necessary for tight fit such that spacing is not more than sixteen (16) inches o.c.
- B. Board shall be fastened securely to supports with screws as specified. Place boards in position with minimum amount of joints. Where free ends occur between supports, back-blocking or furring shall be required. Center abutting ends over supports. Correct work as necessary so that faces of boards are flush, smooth and true. Provide clips or cross furring for attachment as required.
- C. All layers shall be screw attached to furring.
- D. When column finish called for on drawings to be in the same plane as drywall finish layer, maintain even, level plane.

3.8 FINISHING

- A. Taping: A thin, uniform layer of compound shall be applied to all joints and angles to be reinforced. Reinforcing tape shall be applied immediately, centered over the joint, seated into the compound. A skim coat shall follow immediately, but shall not function as a fill or second coat. Tape shall be properly folded and embedded in all angles to provide a true angle.
- B. Filling: After initial coat of compound has hardened, additional compound shall be applied, filling the board taper flush with the surface. The fill coat shall cover the tape and feather out slightly beyond the tape. On joints with no taper, the fill coat shall cover the tape and feather out at least four (4) inches on either side of the tape. No fill coat is necessary on interior angles.
- C. After compound has hardened, a finishing coat of compound shall be spread evenly over and extending slightly beyond the fill coat on all joints and feathered to a smooth, uniform finish. Over tapered edges, the finished joint shall not protrude beyond the plane of the surface. All taped angles shall receive a finish coat to cover the tape and taping compound, and provide a true angle. Where necessary, sanding shall be done between coats and following the final application of compound to provide a smooth surface, ready for painting.
- D. Fastener Depressions: Compound shall be applied to all fastener depressions followed, when hardened by at least two (2) coats of compound, leaving all depressions level with the plane of the surface.

- E. Finishing Beads and Trim: Compound shall be applied to all bead and trim and shall be feathered out from the ground to the plane of the surface. When hardened, this shall be followed by two (2) coats of compound each extending slightly beyond the previous coat. The finish coat shall be feathered from the ground to the plane of the surface and sanded as necessary to provide a flat, smooth surface ready for decoration.
- F. Level of finish for surface exposed to view shall conform to Level 4 of ASTM C 840 and GA-214 of the Gypsum Association.
- G. Drywall construction with defects of such character which will mar appearance of finished work, or which is otherwise defective, will be rejected and shall be removed and replaced at no expense to the City of New York.

3.9 CLEANING AND ADJUSTMENT

- A. At the completion of installation of the work, all rubbish shall be removed from the building leaving floors broom clean. Excess material, scaffolding, tools and other equipment shall be removed from the building.
- B. Work shall be left in clean condition ready for painting or wall covering. All work shall be as approved by Commissioner.
- C. Cutting and Repairing: Include all cutting, fitting and repairing of the work included herein in connection with all mechanical trades and all other trades which come in conjunction with any part of the work, and leave all work complete and perfect after all trades have completed their work.

3.10 PROTECTION OF WORK

- A. Installer shall advise Contractor of required procedures for protecting drywall work from damage and deterioration during remainder of construction period.

END OF SECTION