

SECTION 096813**CARPET TILE****PART 1 GENERAL****1.1 GENERAL REQUIREMENTS**

- A. Work of this Section, as shown or specified, shall be in accordance with the requirements of the Contract Documents.

1.2 SECTION INCLUDES

- A. Work of this Section includes all labor materials, equipment and services necessary to complete the carpet tile as shown on the drawings and/or specified herein, including, but not limited to, the following:
 - 1. Carpet tile.
 - 2. Adhesive.

1.3 RELATED SECTIONS

- A. Concrete sub-floor – Existing.

1.4 QUALITY ASSURANCE

- A. Installer Qualifications: Firm with not less than three (3) years of experience in installation of commercial carpeting of type, quantity and installation methods similar to work of this Section.
- B. General Terminology/ Information Standard: Refer to current edition of "Carpet Specifier's Handbook" by The Carpet and Rug Institute; for definitions of terminology not otherwise defined herein, and for general recommendations and information.
- C. Carpet used on Project must be from same dye lot for each carpet type.

1.5 SUBMITTALS

- A. Product Data: Submit manufacturer's complete technical product data for each type of carpet, cushion and accessory item required.
- B. Samples: Submit full size samples of carpet tile and six (6) inches long samples of each type exposed edge stripping.
- C. Certification: Submit manufacturer's certification stating that carpet materials furnished comply with specified requirements.
 - 1. Include listing of mill register numbers for carpet furnished.
 - 2. Include supporting certified laboratory test data indicating that carpet meets or exceeds specified test requirements.
- D. Maintenance Data: Submit manufacturer's printed maintenance recommendations, including methods and frequency recommended for maintaining carpet in optimum conditions under anticipated traffic and use conditions.

1.6 EXTRA STOCK

- A. Produce and deliver to project at least five (5) percent overrun on calculated yardage. Provide required overrun exclusive of carpet needed for proper installation, waste and usable scraps.

1.7 PRODUCT DELIVERY AND STORAGE

- A. Deliver carpeting materials in original mill protective wrapping with mill register numbers and tags attached. Store inside, in well ventilated area, protected from weather, moisture and soiling.

1.8 WARRANTY

- A. Provide special project warranty, signed by Contractor and Manufacturer (Carpet Mill), agreeing to repair or replace defective materials and workmanship of carpeting work during two (2) year warranty period following substantial completion. Attach copies of product warranty.

PART 2 PRODUCTS**2.1 CARPET TILE**

- A. Provide carpet tile as noted on drawing sheet A-006.00 "Finish Specifications and Glazing Schedule".

2.2 ACCESSORIES

- A. Adhesive for Carpet Tile: Provide release type adhesive as recommended by the carpet tile manufacturer for use with carpet tile specified. Provide adhesive which complies with flame spread rating required for the carpet installation.
- B. Miscellaneous Materials: Provide the types of adhesives and tape, and other accessory items recommended by the carpet manufacturer and Installer for the conditions of installation and use.
- C. Leveling Compound: Latex/Portland cement flashing patching and leveling compound equal to No. 226 with 3701 admixture made by Laticrete or equal made by Mapei, H.B. Fuller or approved equal.

PART 3 EXECUTION**3.1 INSPECTION**

- A. Examine the areas and conditions where carpet tile is to be installed and correct any conditions detrimental to the proper and timely completion of the work. Do not proceed with the work until unsatisfactory conditions are corrected to permit proper installation of the work.

3.2 PRE-INSTALLATION REQUIREMENTS

- A. Floor shall be clean and free of cracks and protrusions. Any gaps or cracks more than 1/16" wide to be filled in with latex leveling compound. Protrusions must be sanded down smooth, the floor cleanly swept and vacuumed if necessary to remove all dust and grit.

1. Coordinate with and comply with recommendations of the Commissioner's Hazardous Materials/Abatement Contractor and for grinding areas where existing flooring has been removed.
- B. Floor temperature shall be 65 deg., at least 24 hrs prior to installation; and 48 hrs. after carpet is installed.
- C. Conduct a moisture test on new concrete deck only. The presence of moisture in the concrete floor will interfere with the curing and subsequent performance of the adhesive. Conduct the test as follows:
 1. Drive a concrete nail a half inch into the floor. Then remove the nail.
 2. Place a small amount of anhydrous calcium chloride or calcium sulphate crystals over the hole.
 3. Cover the crystals and the hole with a piece of flat glass and seal the edges with waterproof tape or putty. Since concrete pourings vary, repeat the test every 1500 sq. ft.
 4. Leave in place 72 hrs. Any color change in the crystals indicates the presence of moisture. Do not apply carpet until slab is free of moisture and meets with approval of carpet adhesive manufacturer.
- D. Sequence carpeting with other work so as to minimize possibility of damage and soiling of carpet during remainder of construction period.

3.3 INSTALLATION

- A. General
 1. Comply with manufacturer's instructions and recommendations. Maintain direction of pattern and texture, including lay of pile.
 2. Adhere all tiles with a full spread of adhesive. Dry-fit cut tiles and apply adhesive to tile back after tile has been cut.
 3. Tiles shall be installed in a monolithic corner to corner manner following arrows printed on back of each tile indicating pile direction. Tiles shall be installed to achieve patterns as directed by the Commissioner.
 4. Vinyl reducer strips shall be used along any necessary open edges so as to maintain the fixed perimeter.

3.4 CLEANING UP

- A. Upon completion of the carpeting installation in each area, visually inspect all carpet installed in that area and immediately remove all dirt, soil, and foreign substance from the exposed face; inspect all adjacent surfaces and remove all marks and stains caused by the carpet installation; remove all packaging materials, carpet scraps, and other debris from the carpet installation to the area of the job site set aside for its storage.

3.5 PROTECTION

- A. In all areas, provide a temporary non-staining paper pathway in the direction of traffic.

END OF SECTION

This Page Left Intentionally Blank