

- NOTES
- REFER TO DRAWING E-001.00 AND E-002.00 FOR ELECTRICAL SYMBOL LIST, ABBREVIATIONS AND GENERAL NOTES.
  - ALL CIRCUITS SHALL BE ENERGIZED FROM ELECTRICAL PANELS ACCORDING TO THE FOLLOWING PANEL LEGEND:  
H#1 - INDICATES PANEL RP2-2HA, CIRCUIT #1
  - FOR ELECTRICAL PANEL LOCATIONS, REFER TO KEY PLAN ON DRAWING E-010.00.
  - REFER TO DETAILS DRAWING FOR NURSE CALL WIRING DIAGRAM.

- KEY NOTES
- ELECTRIC DUCT HEATER WITH INTEGRAL DISCONNECT SWITCH PROVIDED BY MECHANICAL CONTRACTOR. COORDINATE WITH MECHANICAL CONTRACTOR FOR REQUIRED CLEARANCES AND WIRING REQUIREMENTS.
  - PROVIDE RECESSED BACK-BOX AND 3/4" STUB-UP TO ABOVE ACCESSIBLE CEILING FOR FLUSHOMETER SENSOR. COORDINATE WITH PLUMBING CONTRACTOR.
  - LOW VOLTAGE TRANSFORMER FOR FLUSHOMETER VALVES LOCATED ABOVE ACCESSIBLE CEILING, ENERGIZE FROM CIRCUIT DESIGNATED ON PLAN. PROVIDE LOW VOLTAGE WIRING AND CONDUIT TO FLUSHOMETERS AS REQUIRED, MAXIMUM OF 10 FLUSHOMETERS PER TRANSFORMER. COORDINATE WITH PLUMBING CONTRACTOR FOR EXACT SPECIFICATIONS AND WIRING REQUIREMENTS.

THIS PLAN IS APPROVED ONLY FOR WORK INDICATED ON THE APPLICATION SPECIFICATION SHEET. ALL OTHER MATTERS SHOWN ARE NOT TO BE RELIED UPON, OR TO BE CONSIDERED AS EITHER BEING APPROVED OR IN ACCORDANCE WITH APPLICABLE CODES.


PROGRESS  
11-02-2011

DOB EMPLOYEE STAMPS AND SIGNATURES:

DOB BSCAN  
STICKER:

REVISION DATE REASON FOR ISSUE

KEY PLAN :



CLIENT: **HHC** **NEW YORK CITY HEALTH AND HOSPITALS CORPORATION**

CLIENT: LINCOLN MEDICAL AND MENTAL HEALTH CENTER

ARCHITECT: **M J C L** **Architects, PLLC**  
1416 Avenue M, Brooklyn, NY 11230  
Tel.: (718) 339-3390 Fax: (718) 339-3642

ENVIRONMENTAL ENGINEERING CONSULTANT: **Lilker Associates**  
**Consulting Engineers, PC**  
1001 Avenue of the Americas, New York, NY 10018  
tel. 212.695.1000 fax 212.695.1299 www.lilker.com

PROJECT: **NEW CLINIC RENOVATION AT SECOND FLOOR**

DRAWING: **SECOND FLOOR POWER PLAN**

SCALE: 1/4" = 1'-0"  
DRAWN BY: CP  
CHECKED BY: GA  
DATE: 09-06-2011  
JOB #: 21115.00  
DRAWING #: **E-201.00**