



1 SECOND FLOOR REFLECTED CEILING PLAN
SCALE: 1/4"=1'-0"

LEGEND

- NEW 2'X2' ACOUSTICAL CEILING TILE & GRID
- EXISTING CEILING TILE & GRID
- NEW GYPSUM BOARD CEILING
- NEW CURTAIN TRACK
- EXISTING 2'X2' LIGHT TO REMAIN
- 2'X2' RECESSED FLUORESCENT DIRECT / INDIRECT ENERGY EFFICIENT LIGHT
- 2'X2' RECESSED FLUORESCENT DIRECT / INDIRECT ENERGY EFFICIENT LIGHT
- EGGCRATE FLUORESCENT LIGHT FIXTURE
- 7'0" COMPACT FLUORESCENT DOWNLIGHT
- 6'3/4" Ø COMPACT FLUORESCENT DOWNLIGHT
- CLG.&MTD LINEAR FLUORESCENT LIGHT FIXTURE
- UNDER COUNTER LIGHT
- MECHANICAL INTAKE DIFFUSER (SIZE VARIES)
- MECHANICAL SUPPLY AIR DIFFUSER (SIZE VARIES)
- FRAMELESS ACCESS PANEL SIZE AND LOCATION TO BE COORDINATED WITH MEP
- NEW SPRINKLER HEAD
- NEW CLG.&MTD SMOKE DETECTOR PER MEP DWGS
- NEW CLG.&MTD EXT. LIGHT, SHADE INDICATES LIGHTED FACE LENGTH AS REQUIRED.
- NURSE CALL DOME LIGHT
- CEILING GRID STARTING POINT
- EXISTING CEILING OBJECT
- CEILING HEIGHT A.F.F.

GENERAL NOTES:

1. CEILING HEIGHT SHALL BE +8'-0" AFF. UNCL.
2. REFER TO DWG A-110.00 FOR CEILING INSTALLATION DETAILS
3. THE CONSTRUCTION OF NEW WORK, MORE OR LESS QUANTITY MAY BE REQUIRED AND SHALL BE PROVIDED BY THE CONTRACTOR AT NO ADDED COST TO OWNER.
4. FOR LIGHTING FIXTURES SCHEDULE SEE ELECTRICAL DRAWINGS.
5. EXISTING SOFFITS THAT ARE REMAINING SHALL BE PROTECTED DURING CONSTRUCTION.
6. ANY CEILING TILES OR MEP ITEMS SCHEDULED TO BE REINSTALLED IN PLACE THAT ARE DAMAGED BY THE CONTRACTOR DURING DEMOLITION SHALL BE REPLACED AT THE CONTRACTOR'S EXPENSE.
7. PROVIDE NEW ACCESS PANELS AS REQUIRED

DOB EMPLOYEE SIGNATURES

DOB SSCON STUCKER

06-25-2012

ISSUED TO DOB

11-02-2011

ISSUED FOR OWNER REVIEW

REVISION DATE

REASON FOR ISSUE

KEY PLAN :

AREA OF WORK "202"

CLIENT

NEW YORK CITY HEALTH AND HOSPITALS CORPORATION

CLIENT

LINCOLN MEDICAL AND MENTAL HEALTH CENTER

ARCHITECT:

M J Architects, PLLC

ENVIRONMENTAL ENGINEERING CONSULTANT:

Lilker Associates Consulting Engineers, PC

PROJECT:

NEW CLINIC RENOVATION AT SECOND FLOOR

SCALE: 1/4"=1'-0"

DRAWN BY: CAD

CHECKED BY: VC

DATE: 09-06-2011

JOB #: 21115.00

DRAWING #:

A-110.00

9 of 36